Secta. II-37—100,000—21-6-52.

Food (1951) Department.

(1) SERIES.

G.O. No. (1) 757

Dated 13-8-51

[Despatch Abstract.]

AGRICULTURE : GROW MORE FOOD : COMPOST : MODEL SIEVE FOR THE REMOVAL OF HARMFUL MATERIALS FROM COMPOST : ESTIMATE AND BLUE PRINT : COMMUNICATED TO MUNICIPALITIES AND PANCHAYAT BOARDS.

GOVERNMENT OF MADRAS
Abstract
**

AGRICULTURE - Grow More Food - Compost - Model sieve for the removal of harmful materials from compost - Estimate and blue print - Communicated to municipalities and panchayat boards.

- -

Food Department.

G.O. (Ms) No. 757. Dated, the 13th August 1949
READ - the following:-

From the Director of Agriculture, No. L1-990/49 dated the 16th July 1949.

- - - - - -

ORDER:

It has been brought to the notice of Government that compost in several places is not popular because it is not free from glass pieces, stones, etc. The estimate and blue print of a model sieve designed by the Research Engineer, Coimbatore, for the removal of glass pieces, brick bats, tin pieces, etc., from compost are communicated to all municipalities and major panchayat boards, for adoption in their schemes for the manufacture of town compost.

(By order of His Excellency the Governor)

M.A. KUTTALALINGAM PILLAI.
Secretary to Government.

To the Director of Agriculture.
To the Inspector of Municipal Councils and Local Boards.
To the Director of Public Health.
To the Registrar of Co-operative Societies.
To the Commissioner of the Corporation of Madras (through the Mayor)
To the Commissioners of all Municipalities (through the Chairmen)
To the Presidents of all Panchayat Boards.
To the Superintendent, Government Press (with enclosure).
Copy to the Local Administration Department.

ABSTRACT ESTIMATE.

Estimate for making a sieve 6 x 3 to remove glass pieces, brick bats and tin pieces from compost.

Description of work and quantity.	Item no.in the schedule of rates.	Rate Rs.	per	Amount
-1-	-2-	-3- Rs	-4-	-5- Rs
Country wood scantlings For frame work 2-6-0 0-30-2) -do- 2-3-0 0-30-2) Supports to wove wire 2-3-0 0-30-1 Struts 2-5-3 0-30-1½) Cross piece to struts, 1-3-3 0-30-1½)	0.75 0.13 0.13 0.43 --- 1.31 c.ft.	Local rate. 7.8.0	1 c.ft.	9.13.0
Country wood reeper 2" x 1" for fixing wire gauge to frame work 2-6-0 2.3.0	12 Rfts 6 Rfts 18 "	0.1.6	Reft	1.11.0
Hexagonal bolt and nut 4" x 1/2"	2 Nors.	0.4.0	each	0. 8.0
Galvanised sove wire 18G 4,meshes per lineal inch for screen 1-6-0 x 3.0	18.sq.ft.	0.12.0	sq.ft.	13. 8.0
Wood scress 2' long for fixing wove wire to frame with reppers.	2 xoz.	0.12.0	doz	1. 8. 0
Labour for making the screen.	3	3. 0.0	each	9. 0. 0
Painting with chocolate paint, 2 coats the wood only, sundries, cartage on timber, etc.		carpenters - local rate.		9. 0. 0
			Grand total etimate	45-0.0